

1 031089

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,494.0000  
SE NW SE, SEC. 6, T. 20 S, R. 24 W/E  
1650 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Lease Name Betz Well # 1

Operator: Vess Oil Corporation

County Ness 143.03

Name & Address 8100 E. 22nd Street North, Bldg. 300  
Wichita, KS 67226

Well Total Depth 4401 feet

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 802

Abandoned Oil Well            Gas Well            Input Well            SWD Well            O&A X

Other well as hereinafter indicated           

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 3 Month: 8 Year: 1990

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1567-1612'  
1st plug at 1610' with 50 sx cement,  
2nd plug at 840' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement.

           Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 8:15 p.m. Day: 3 Month: 8 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 1610' with 50 sx cement,

2nd plug at 840' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

AUG - 9 1990

CONSERVATION DIVISION  
Wichita, Kansas

8-9-90

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE: 8-23-90

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 29031

EFFECTIVE DATE: 7-29-90

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas 135-23,494

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date July 26 1990  
month day year

SE NW SE Sec 6 Twp 20 S, Rg 24 XX East West

OPERATOR: License # 5030  
Name: Vess Oil Corporation  
Address: 8100 E. 22nd Street North, Bldg. 300  
City/State/Zip: Wichita, KS 67226  
Contact Person: W. R. Horigan  
Phone: 316-682-1537

1650 feet from South line of Section  
1650 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039  
Name: L.D. Drilling, Inc.

County: Ness  
Lease Name: Betz Well #: 1  
Field Name: Hair West

Well Drilled For: Well Class: Type Equipment:  
XX Oil XX Inj X Infield XX Mud Rotary  
XX Gas XX Storage XX Pool Ext. XX Air Rotary  
XX OAWO XX Disposal XX Wildcat XX Cable  
XX Seismic; XX # of Holes

Is this a Prorated Field? XX yes XX no  
Target Formation(s): Mississippi  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2330 est. feet MSL

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Domestic well within 330 feet: XX yes XX no  
Municipal well within one mile: XX yes XX no  
Depth to bottom of fresh water: 500'  
Depth to bottom of usable water: 750'  
Surface Pipe by Alternate: XX 1 XX 2  
Length of Surface Pipe Planned to be set: 800'  
Length of Conductor pipe required: N/A  
Projected Total Depth: 4400'  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:  
XX well XX farm pond XX other

Directional, Deviated or Horizontal wellbore? XX yes XX no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: N/A  
Will Cores Be Taken?: XX yes XX no  
If yes, proposed zone: \_\_\_\_\_

Exp. 1/24/91

D & A P.M.  
AFFIDAVIT

770' Alt. RECEIVED  
STATE OF KANSAS COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,  
AUG - 9 1990

Pusher Greg Davidson

SPUD DATE 7-27-90 INIT. C.A.

LENGTH SURFACE PLANNED 800'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbbls. when done bbbls.

RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 7/8" @ 802 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T-1567 B-1612 ELEVATION \_\_\_\_\_

TD 4400 FORMATION Miss

KAN PIPE	@	DV TOOL	ALT II DONE
			SX Y N
Arbuckle Plug	@		Ft. W/ <u>SX</u>
Hug./Council	@		Ft. W/ <u>SX</u>
Anhydrite Base	@	<u>1610</u>	Ft. W/ <u>50 XSX</u>
1/2 Base Anyh.	@		Ft. W/ <u>SX</u>
1/2, 1/2 Plug	@		Ft. W/ <u>SX</u>
Bottom Surface	@	<u>840</u>	Ft. W/ <u>50 SX</u>
40' Plug	@	<u>40</u>	Ft. W/ <u>10 SX</u>

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL \_\_\_\_\_ SX (Irr. Well Pond \_\_\_\_\_)  
TECHNICIAN SA DATE 8/3/90 Hauling \_\_\_\_\_  
TYPE OF CEMENT 60/40 690

STARTING TIME 3: (AM/PM) DATE 8-3-90  
COMPLETION TIME 8:15 (AM/PM) DATE 8-90  
CEMENT COMPANY Allied