

To: 1 090185
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N., Bldg. 300
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Saturn Well Service License Number 3641
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2:25 p.m. Day: 23 Month: 4 Year: 19 92

Plugging proposal received from Bessie
(company name) L.D. Drilling (phone) 316-793-5831

work: 4 1/2" at 4433' w/175 sx cement, Perfs at 4435-39'
1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 23 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 175 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2590' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

1 (circle) observe this plugging.

INVOICED
DATE 5-5-92
INV. NO. 35157

Signed [Signature]
(TECHNICIAN)

4-23
API NUMBER 15-135-23,504.0000 179R
SW SW NW, SEC. 36, T. 20 S, R 26 W/E
2970 feet from S section line
4950 feet from E section line
Lease Name McVicker "KS" Well # 1
County Ness
Well Total Depth 4439 144.26 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 836