

1 050972

12-11-87

API NUMBER 15-135-23,194.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW NE, SEC. 25, T. 20 S, R. 21 W/Ex
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2970 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6151

Lease Name Martin Well # 1

Operator: Kansas Crude, Inc.

County Ness 142.64

Name & Address 202 Wolcott Building

Well Total Depth 4389 feet

Hutchinson, KS 67501

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 471

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Lobo Drilling Company License Number 5864

Address Box 877, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 11 Month: 12 Year: 1987

Plugging proposal received from Ervin Neighbors

(company name) Lobo Drilling Company (phone) 816-792-7476

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2230' GL
Anhydrite 1414-43'

1st plug at 1440' with 50 sx cement, 2nd plug at 820' with 80 sx cement,

3rd plug at 500' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 11 Month: 12 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement,

2nd plug at 820' with 80 sx cement,

3rd plug at 500' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

12-15-87
DEC 15 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if desired, observe this plugging.)

DATE 12-15-87

INV. NO. 19294

Signed Richard W. Lacey
(TECHNICIAN)

15.135.23194.0000 NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: 12 month 7 day 87 year

API Number 15-135-23,194.0000

OPERATOR: License # 6151
Name KANSAS CRUDE, INC.
Address 202 Wolcott Building
City/State/Zip Hutchinson, Kansas 67501
Contact Person Tim Shaffer
Phone 316/665-7201

C-S/2 S/2 SW NE Sec. 25 Twp. 20 S. Rg. 21
2970-2909 Ft. from South Line of Section
1980 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Ness

CONTRACTOR: License # 5864
Name LOBO DRILLING COMPANY
City/State Great Bend, Kansas 67530

Lease Name Martin Well # 1

Well Drilled For: Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Ground surface elevation feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 100
Depth to bottom of usable water 440

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 460

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Conductor pipe required
Projected Total Depth 4380 feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Nov. 30, 1987 Signature of Operator or Agent Sally R. Byers Title Agent

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 460 feet per Alt. X

This Authorization Expires 6-1-88 Approved By REA 12-1-87

ESTIMATED DATE: 12-6-87

Spud 12-6-87

460' of 8 5/8"

NO WW

C-S/2 S/2 SW NE Sec. 25 Twp. 20 S. Rg. 21 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Material/Notes. Includes entries for 1st through 5th plugs and Rathole/Mousehole to surface minus 5 feet.

Handwritten log entries: IRVIN NEIGHBORS, TD 2489 FORMATION, SURFACE PIPE 8 5/8 @ 471, ANHYDRITE 1443 ELEVATION 2230, STARTING TIME & DATE 11:00am 12-11-87, COMPLETION TIME & DATE 2:00pm 2-11-87, 1st PLUG @ 1440 FT. W/ 50 SX, 2nd PLUG @ 820 FT. W/ 80 SX, 3rd PLUG @ 500 FT. W/ 50 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Allied, TECHNICIAN Lacey witnessed 6/40 w/ 6%

DEC 15 1987

Wichita, Kansas