

9-18

To: 1 030977
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,285.0000
100' E of
C N/2 NE, SEC. 30, T 17 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 6759

4620 feet from S section line
1220 feet from E section line

Operator: William N. Bucklin, III
Name & Address 150 California Street, Suite 300
San Francisco, CA 94111

Lease Name Brenner Well # 4
County Ness 141.12

Well Total Depth 4342 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 18 Month: 9 Year: 19 88

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-1201
Elevation 2228'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1521-55'

1st plug at 1530' with 50 sx cement, 2nd plug at 780' with 80 sx cement,

3rd plug at 270' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 p.m. Day: 18 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 780' with 80 sx cement,

3rd plug at 270' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 10-6-88

INV. NO. 22519

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: 9 12 88 month day year

API Number 15-135-23,285.0000 100' E of C. N/2 NE Sec. 30 Twp. 17 S, Rg. 21W East West

OPERATOR: License # 6759 William N. Bucklin, III 150 California St., Ste. 300 San Francisco, CA 94111 Mr. William N. Bucklin, III 415-433-7100

CONTRACTOR: License # 5302 Red Tiger Drilling Co. Wichita, Kansas 67202

Well Drilled For: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventual changes made to locations. Date 9-7-88 Signature of Operator or Agent

For KCC Use:

Conductor Pipe Required 200' feet; Minimum Surface Pipe Required 200' feet per Alt. X(2) This Authorization Expires 3-7-89 Approved By LKM 9-7-88

EFFECTIVE DATE: 9-12-88 Set 250' of 8 5/8 on 9-12-88

100' E of G. N/2 NE Sec. 30 Twp. 17 S, Rg. 21W East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (ft), Formation, Size (SX), and Material (e.g., 60-40 poz., 6% gel)

(2) Rathole to surface minus 5 feet

(b) Mousehole to surface minus 5 feet

Handwritten log: PUSHER Mike Wagoner TD 4342 FORMATION MISS SURFACE PIPE 8 5/8 @ 253 ANHYDRITE 15-21 ELEVATION 2228 5-18-88 STARTING TIME & DATE 10:00 AM 5-18-88 COMPLETION TIME & DATE 1:30 PM 1st PLUG @ 1530 FT. W/ 50 SX 2nd PLUG @ 790 FT. W/ 80 SX 3rd PLUG @ 270 FT. W/ 40 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ Hawk CEMENT COMPANY 60/40 Permit called TECHNICIAN S.H.

RECEIVED STATE CONSERVATION COMMISSION SEP 22 1988 CONSERVATION DIVISION Wichita, Kansas