

1 050564

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,076

C SE NE, SEC. 24, T 20 S, R 21 W

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5331

Lease Name Isern Well # 1

Operator: Braden-Deem, Inc.

County Ness 142.91

Name & Address 125 North Market, Suite 1250

Well Total Depth 4397 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 1 Month: July Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4396' Perfs at 4384-91'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:15 pm Day: 1 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10

sx gel, 1 sack hulls and 150 sx cement.

Maximum pressure 800 psi and shut in 300 psi

RECEIVED CORPORATION COMMISSION

Remarks: Recovered 2400' 4 1/2" casing. Used 160/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

CONSERVATION DIVISION
Wichita, Kansas

DATE 7-17-85

Signed Paul Luthi (TECHNICIAN)

INV. NO. 8991