

1 121001

12-27

15.135.20129.0000  
Drill completion date 3/24/68

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
C SE SE 24, T 20 S, R 21 W/E  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Isern Well # 2

Operator: D.R. Lauck Oil Company, Inc.  
Name & Address 221 S. Broadway, Ste. 400  
Wichita, KS 67202

County Ness  
Well Total Depth 4362 141.77 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 282

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 27 Month: 12 Year: 1994

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage (phone) 316-938-2943

were: 7" at 4352' w/100 sx cement, PBDT 4326', Open hole 4352-62'

1st plug sand back to 4300' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1400', 3rd plug pump 80 sx cement at 700',

4th plug pump 80 sx cement at 310', 5th plug pump 15 sx cement at 40'.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 12 Year: 1994

ACTUAL PLUGGING REPORT Shot 7" casing at 2000', 1400', 1000', and 700'-couldn't pull casing.

1st plug sanded 7" casing back to 4300' and dumped 7 sx cement on top of sand through bailer,

2nd plug pumped into 7" casing with 200 sx cement. Pumping pressure 0-200 psi and shut in vacuum.

3rd plug pumped into 10 3/4" X 7" annulus with 150 sx cement. Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed *Dean Rubini*  
(TECHNICIAN)

DATE 1-9-95

INV. NO. 42016

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 9 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS