

To: 1 080008  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 135-20,335.0000  
150' E of  
SW NW, SEC. 20, T 20 S, R 21 W/X  
3300 feet from S section line  
4470 feet from E section line

12-26

TECHNICIAN'S PLUGGING REPORT

Operator License # 6016  
Operator: Condor Energy, Inc.  
Name: \_\_\_\_\_  
Address P.O. Box 108  
Great Bend, KS 67530

Lease Name Trimmell Well # 1  
County Ness  
Well Total Depth 4405 143.16 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 288.81

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 26 Month: 12 Year: 1995

Plugging proposal received from John Remmert  
(company name) Condor Energy Inc. (phone) 316-792-1340

Work: 5 1/2" at 4400' with 150 sx cement. Perfs at 4372-78, 4378-84'  
1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,  
2nd plug shoot at 650' and pump 80 sx cement,  
3rd plug shoot at 305' and pump 90 sx cement, circulate cement.

STATE CORPORATION COMMISSION  
RECEIVED  
JAN 05 1996  
WICHITA, KANSAS

Plugging Proposal Received by Kevin Strube  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3 p.m. Day: 26 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand through bailer,  
Shot at 1420' and 650'.  
2nd plug shot at 650' and pumped 80 sx cement, displaced to 375',  
3rd plug shot free at 305' and pumped 90 sx cement, cement circulated,  
4th plug topped off with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 305' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
JAN 12 1996  
observe this plugging.

Signed Kevin D Strube  
(TECHNICIAN)

DATE \_\_\_\_\_  
INV. NO. 44564