

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don Moore Assoc., Inc.

Complete Address: 918 Central Bldg., Wichita, Kansas

Lease Name Sifers Well No. # 2

Location NW SW SW Sec. ²⁶16 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3646

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 7:00PM Day 26th Month June Year 1964

The Above well was plugged as follows:

264' of 8 5/8" surface pipe, cement circulated. 3500' of 4 1/2" long string,
cemented with 125 sacks. Plug back to 3520'. Top perforation 3250'. Plug
was pushed to 3200', and rock bridge, and cemented with 3 sacks. Hole
was squeezed with 15 sacks of Gel-Mud and 75 sacks of cement, pumped
into surface pipe, through an 8 5/8" swage, to a pressure of 400 lbs.
A wiping plug was run between the mud and the cement. This cementing
was done by Sun Cementing Company.

2918' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/29/64

INV. NO. 9383-14

Signed: Archie Elving
Well Plugging Supervisor