

*n*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 17 1966  
1-17-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name Linke Well No. #1

Location C NW NE NW Sec. 27 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 2026'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated: This is a lost hole. Surface pipe parted at 204'

Plugging Contractor: Abercrombie Drilling, Inc.

Address: 801 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour 4:00PM Day 14th Month Jan. Year 1966

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid level in the hole was at 35'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 200', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing bridged with hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1/17/66

INV. NO. 2614-41