

KANSAS

AL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graves Drlg. Co. Inc.
Complete Address 505 Union Center Wichita, Ks 67202
Lease Name Gates Well No. 1
Location C SE/SE/SW Sec. 27 Twp. 21 Rge. 13 (E) (W)
County Stafford Total Depth 3689
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Southwest Casing Pulling Co. Inc.
Address Box 364 Great Bend, Ks License No. 399
Operation Completed: Hour 10:30 AM Day 9 Month 5 Year 1970

The above well was plugged as follows:

250 ft. of 8 5/8 surface pipe cemented with 205 sacks. 3689 ft. of
5 1/2 long string cemented with 100 sacks. Open hole. Sand back to
3670 ft., 30 gals sand & 5 sacks cement with bailer. Pulled 2800 ft.
of 5 1/2. Pumped 2 sacks hulls, 15 sacks gel., release plug, 90 sacks
50-50 pos. & 4 % gel. Allied Cement Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/11/70

INV. NO. 1860-u

Signed: *D. Russell B. Dunster*
Well Plugging Supervisor