

15.135.21893.0000

KANSAS

FORM CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 135-21,893 (of this well)Operator's Full Name TEXICO, INC.Complete Address BOX 2420 - TULSA, OKLAHOMA.Lease Name B. L. HOSS Well No. #1Location SW-SW Sec. 9 Twp. 20 Rge. 24 (E) (W) WCounty NESS Total Depth 4509 FEAbandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereafter indicated Plugging Contractor RAINS + WILLIAMSON OIL CO. INC.Address 435 PAGE COURT - 220 W. DOUGLAS - WICHITA, Ks. License No. Operation Completed: Hour 8:30 ^{PM} Day 23 Month OCT Year 1980The Above well was plugged as follows: 100 ^{ft} COMMON - 3% CA-CL.8 5/8" 605 ^{ft} SP. CUM 270 ^{ft} HALLIBURTON LIGHT - 3% CA-CL.ORDERED 165 ^{ft} 50 ^{ft} POZMIX 2% GEL. + 8 5/8" PLUG. - ELV. 2324 K.B.SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.1ST PLUG. @ 4390 ^{ft} 100 ^{ft} COMMON.2ND PLUG. @ 800 ^{ft} 100 ^{ft} COMMON.3RD PLUG. @ 420 ^{ft} 100 ^{ft} COMMON.4TH PLUG. → SOLID BRIDGE HULLS + PLUG. @ 410 ^{ft} 100 ^{ft} COMMON.5TH IN RAT HOLE.CEMENTED BY HALLIBURTON CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

NOV - 13 1980

Signed: Marion Schmidt

DATE

Well Plugging Supervisor

INV. NO.

3564-WRECEIVED
STATE CORPORATION COMMISSION

11-3-80 NOV - 3 1980

CONSERVATION DIVISION
Wichita, Kansas