

15.135.00099.0000

CP-3

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
8-20-62 AUG 20 1962  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pickrell Dtg Co  
Complete Address: ~~280x~~ 2820 Paseo Great Bend, Kansas  
Lease Name Mc Creight Well No. A-1  
Location CNW NW Sec. 9 Twp. 20 Rge. (E) (W) 24  
County Ness Total Depth 4494  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Forbes Casing Pulling  
Address: Great Bend, Kans License No. 49  
Operation Completed: Hour 7PM Day 16 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 283' circulated with cement - 5 1/2" 4466' with 100 sax cement, Perf 4322'  
Filled with sand to 4300', set 4 sax cement with dump bailer, pulled 2500'  
5 1/2" to 500', circulated hole with heavy gel mud through 5 1/2" at 500' ( 15 sax Gel  
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 210', displaced 20  
sax cement through 5 1/2" at 210', heavy mud to 35', set bridge and 10 sax cement  
to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/20/62  
INV. NO. 5556-4

Signed: [Signature]  
Well Plugging Supervisor