

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-135-20179.0000 (of this well)

Operator's Full Name PALOMINO PETROLEUM

Complete Address 500 INSURANCE BUILDING WICHITA, KANSAS 67202

Lease Name MC-CREIGHT Well No. # 1

Location SW-NE- Sec. 9 Twp. 20 Rge. 24 (E) (W) W

County NESS Total Depth 4430 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor PIPE PULLERS INC.

Address BOX 128 ELLENWOOD, KANSAS License No. 462

Operation Completed: Hour 1:00 P.M. Day 11<sup>th</sup> Month JULY Year 1979

The above well was plugged as follows:

8 5/8" 288<sup>FE</sup> SP. 155<sup>SH.</sup> - 4 1/2" 4420<sup>FE</sup> - 150<sup>SH.</sup>  
PERF - 4346' to 4342' - NO BOTTOM PLUG. - 4 1/2" CASING  
COLLAPSED AND PIPE PULLERS COULD NOT GET BAILEY BELOW  
1127<sup>FE</sup> (SAND CAVED IN) PIPE PARTED AT 1127<sup>FE</sup> AND RECOVERED  
1127<sup>FE</sup>. (ORDERED) 140<sup>SH.</sup> 50% POZNIX 4% GEL. - 20<sup>SH.</sup> GEL. - 3<sup>SH.</sup> HULLS.  
PUT IN - 2<sup>SH.</sup> HULLS - 5<sup>SH.</sup> GEL. - 70<sup>SH.</sup> CMT. - 5<sup>SH.</sup> GEL.  
AND 70<sup>SH.</sup> CMT. - MAX. PRESSURE - 750<sup>LBS.</sup> - SHUT DOWN 550<sup>LBS.</sup>  
CEMENTED BY FULLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7-12-79  
INV. NO. 0001-W

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1979 Signed: Medion Schmidt  
Well Plugging Supervisor

CONSERVATION DIVISION  
Wichita, Kansas