

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

OCT 4 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drlg Co

Complete Address: 705 4th Natl Bk Bldg. Wichita, Kansas

Lease Name Slagle Well No. 2

Location C SE NE Sec. 8 Twp. 20 Rge. 24 (E) (W)

County Ness Total Depth 4411

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase Kansas License No. 436

Operation Completed: Hour 2pm Day 30 Month Sept Year 1965

The Above well was plugged as follows:

TD 4411 8 /5/8 set at 274 5 1/2 set at 4394

Sand to 4380 topped with 4 sax cement with dump bailer

Shot 5 1/2 and pulled same to 600' and cir with 10 sax jell mud, pulled same to 500' and

displaced 20 sax cement, pulled pipe to 275' and displaced 20 sax cement, pilled pipe

out of hole, built rock bridge at 40' and topped with 10 sax cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Arthur P. Leiker
Well Plugging Supervisor

INVOICED

DATE 10/4/65

INV. NO. 1914-W