

15 135.21169.0000

R

RECEIVED
Form CP-3
STATE CORPORATION COMMISSION
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 10 1976
3-10-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,169 (of this well)

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Suite 205, Wichita, Kansas

Lease Name Hair-Lundy Well No. 2

Location 150' E of SW NE Sec. 2 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4457'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 5 P Day 9 Month 3 Year 1976

The above well was plugged as follows:

RTD 4457' 8 5/8 csg set 303' cwc 200 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3-10-76

INV. NO. 2876-W