

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1977
3-16-77
CONSERVATION DIVISION
Wichita, Kansas
(office of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,292

Operator's Full Name Thunderbird Drilling, Inc.
Complete Address Box 18407, Wichita, Kansas
Lease Name Putman "B" Well No. 4
Location C SE SW Sec. 36 Twp. 20 Rge. (E) (W) 26
County Ness Total Depth 4454'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 1:30 A Day 15 Month 3 Year 1977

The above well was plugged as follows:

RTD 4454' 8 5/8 csg set 313' cwc 185 sx. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.
Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Masney
Well Plugging Supervisor

DATE 3-16-77
INV. NO. 4804-W