

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

REVISED 6-1-68

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135 -21437.0000 (of this well)

Operator's Full Name Inco Oil Co.

Complete Address Box 52069, Tulsa, Oklahoma

Lease Name McVickers Well No. 1

Location C SW NE Sec. 36 Twp. 20 Rge. (E) (W) 26

County Ness Total Depth 4431'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DNB Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:30 P Day 5 Month 3 Year 1978

The above well was plugged as follows:

RTD 4431' 8 5/8 csg. set 322' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 3-7-78

INV. NO. 6276.0