

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company  
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Lease Name Wells "D-E" Unit Well No. I  
Location 150' SE of C SE SW Sec. 25 Twp. 20 Rge. (E) (W) 21  
County Ness Total Depth 4465'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Russ Casing Pulling  
Address Box 1082 Great Bend, Kansas 67530 License No. 623  
Operation Completed: Hour 10 A Day 6 Month 3 Year 72

The above well was plugged as follows:

Total Depth 4465' 8 5/8 csg set at 258' cwt: 160 sk.  
4 1/2 csg set at 4464' cw 100 sk cmt.  
4 1/2 csg PETD 4391' with perf. (4334)  
Filled 4 1/2 csg W/sd (4300-4391) dumped 4 sk cmt W/dump bailer. (4265-4300)  
Cutoff and recovered 495' of 4 1/2 csg.  
Pumped down 8 5/8 csg with 10 sk gel & water W/200 lbs hulls, released 8 5/8 plug  
and pumped 100 sk 50-50 poz cmt W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3-10-72

INV. NO. 5315-10