

KANSAS

70
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Barnett Oil Company

Complete Address: 411 1st Nat'l Bank Bldg. Wichita, Kansas

Lease Name Martin "C" Well No. 1

Location C SE SE Sec. 25 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4413

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: K & E Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 3 A Day 7 Month 9 Year 1967

The Above well was plugged as follows:

RTD 4413' 8 5/8 csg set at 260' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 620' and displaced 100 sc cem. thru drill pipe. Heavy mud to 270' set cementing plug and displaced 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Rev. E. Massey
Well Plugging Supervisor

DATE 9/8/67
WELL NO. 6280-W