

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas
Lease Name Brenner Well No. 1
Location C NE NE Sec. 30 Twp. 17 Rge. (E) (W) 21
County Ness Total Depth 4305'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor SW Casing Pulling Company
Address Box 405 Great Bend, Kansas 67530 License No. 399
Operation Completed: Hour 11:45 A Day 30 Month 10 Year 1973

The above well was plugged as follows:

Total Depth 4305' 8 5/8 csg set at 273' cwc

5 1/2 csg set at 4301' cw 75 sk cmt

Filled 5 1/2 csg W/sd (4275-4305) dumped 5 sk cmt with dump bailer. (4240-4275)

Cutoff and recovered 3260' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls -- 70 sk cem. -- 8 sk

gel & water -- released 8 5/8 plug and pumped 50 sk cmt by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/2/73

INV. NO. 8106-47

Signed: Leo F. Massey
Well Plugging Supervisor