

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,481 (for this well)

RECEIVED
SIA... CONSERVATION COMMISSION
JUL 25 1978
CONSERVATION DIVISION
Wichita, Kansas
7-25-78

Operator's Full Name Hummon Oil Co.

Complete Address 1725 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Brenner Well No. 1

Location C SE NE Sec. 30 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4370'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated _____

Plugging Contractor D. R. Lauck Drlg.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 9:45 A Day 23 Month 7 Year 1978

The above well was plugged as follows:

RTD 4370' 8 5/8 csg set 387' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Messing
Well Plugging Supervisor

DATE 7-25-78

INV. NO. 7733-W