

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 8 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Oilfield Supply and Trading, Inc.

Complete Address 430 Greenwood Wichita, Kansas 67211

Lease Name Rowland Well No. 1

Location SE SW Sec. 24 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4444

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Comstock

Address Stafford, Kansas License No. 490

Operation Completed: Hour 2P Day 2 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4444' 8 5/8 csg set at 230' cwc

4 1/2 csg set at 4444' cw 100 sk cmt and perf. (4442)

Filled 4 1/2 csg w/sd (4100-4125) Dumped 4 sk cmt W/dump bailer. (4060-4100)

Cutcff and recovered 2100' of 4 1/2 csg.

Circulated gel (15 sk) at 750' thru 4 1/2 csg.

Displaced 70 sk poz 6% at 500' thru 4 1/2 csg.

Displaced 20 sk poz 6% at 210' thru 4 1/2 csg.

Set plug at 30' & cemented W/10 sk to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Massey
Well Plugging Supervisor

DATE 6/8/70
INV. NO. 2008-4