

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name D. R. Lauck Oil Co. Inc.,

Complete Address: 301 S. Broadway Wichita, Kansas

Lease Name Rowland Well No. 1

Location C SE SW Sec. 24 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4445

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Co. Tools

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 12 M Day 29 Month 4 Year 1968

The Above well was plugged as follows:

RTD 4445' 8 5/8 csg set at 317' cwc 185 sc. Cem. Mat. 100 sc of 6% 50-50 poz cement.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 310' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy Mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 5/2/68

INV. NO. 4676-4