

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-25794-00-01  
Spot: SENWSENW Sec/Twnshp/Rge: 29-12S-17W  
1860 feet from N Section Line, 1734 feet from W Section Line  
Lease Name: A AND A KARLIN Well #: 1  
County: ELLIS Total Vertical Depth: 3775 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3775		150 SX
SURF	8.625	226		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2017 9:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM, INC. DBA Phone: (620) 583-5527

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 17 sx gel and 300 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/20/2017 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Circulated cement through DV Tool. Ran tubing to 3600' and pumped 17 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 200 sx cement w/200 # hulls. Had good returns of cement to pit. POOH. Hooked to braden head with 300 psi. No fluid moved. Topped off casing with 20 sx cement. Casing stayed full.

GPS: 38.98191 -099.23621

Perfs:

Top	Bot	Thru	Comments
3712	3718		
3706	3712		
3690	3712		

KCC WICHITA  
DEC 04 2017  
RECEIVED

INVOICED

JAN 02 2018

Remarks: COPELAND ACID AND CEMENTING TICKET # 45253

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

NOV 27 2017

Form CP-2/3