

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-10110-00-00
Spot: SENW Sec/Twnshp/Rge: 35-31S-40W
3363 feet from S Section Line, 3259 feet from E Section Line
Lease Name: G L HAYWARD B Well #: 1-35
County: MORTON Total Vertical Depth: 5460 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		720		
CIBP		5177		WITH 2 SX CMT
CIBP		5460		
CIBP		5625		
CIBP		5730		
CIBP		5800		
DVT		3113		
PROD	4.5	5900	0	WITH 250 SX CMT
SURF	8.625	689		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/07/2017 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: BRIAN J MCCOY Company: EDISON OPERATING Phone: (316) 214-3658

Proposed Plugging Method: CIBP @ 5360' WITH 2 SX CMT. RUN CBL FROM 3150'. SPOT 25 SX CMT AT 1700'. SET CIBP @ 750' +/- . TEST CASING T 500#. IF CMT IS ABOVE SURFACE CASING SHOE, FILL THE 4 1/2" WITH CMT FROM 700' TO SURFACE THEN FILL THE ANNULUS WITH CMT. IF CMT IS BELOW SURFACE CASING SHOE, PERFORATE AT 725' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2017 3:30 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 5177' WITH 2 SX CMT. PLUG AT 1712' WITH 25 SX CMT. SET CIBP @ 720'. PRESSURE TESTED CASING TO 500#. CIRCULATE CMT FROM 720' TO SURFACE WITH 60 SX CMT. FILL 8 5/8" X 4 1/2" ANNULUS WITH 5 SX CMT. (Perf)

Perfs:

Top	Bot	Thru	Comments
5812	5814		CHESTER
5743			L. MORROW
5672	5674		MORROW
5494	5496		MORROW
5408	5412		MORROW

INVOICED
JAN 02 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
NOV 20 2017
KCC DODGE CITY

Signed Heith Walsh