

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24709-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 28-19S-14W
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: E T T R Well #: 4-28
County: BARTON Total Vertical Depth: 2335 feet

Operator License No.: 8631
Op Name: FARRIS, DONNA DBA FARRIS WELL S
Address: 519 N. POST RD.
MIDWEST CITY, OK 73130

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2348		150 SX
SURF	8.75	795		400 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/13/2017 8:00 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: LARRY ROMME Company: FARRIS, DONNA DBA FARRIS WE Phone: (620) 626-7100

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 600'. Ran tubing to 1800' and pumped 40 sx cement w/100 # hulls.
Pulled tubing to 1200' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 600'.
Circulated cement to surface with 70 sx cement. Shut valve and circulated cement to surface on surface pipe with 110 sx cement. Pulled tubing and topped off with 10 sx cement.

GPS: 38.37166 -098.88400

Perfs:

KCC WICHITA
DEC 04 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

INVOICED
JAN 02 2018

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

NOV 14 2017