

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24562-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 30-17S-11W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: BERAN Well #: 2  
County: BARTON Total Vertical Depth: 3413 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3412	1710	150 SX
SURF	8.625	269		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2017 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/30/2017 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement. Cut casing at 1710'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 1000' and pumped 50 sx cement w/100 # hulls. Pulled casing to 700' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250'. Circulated cement to surface with 100 sx cement. Pulled casing and topped off with 25 sx cement.

GPS: 38.53723 -098.58940

Perfs:

Top	Bot	Thru	Comments
3293	3298		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

INVOICED

JAN 02 2018

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

DEC 01 2017

Received  
KANSAS CORPORATION COMMISSION

DEC 20 2017

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3