

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-30150-00-00  
Spot: SENENW Sec/Twnshp/Rge: 7-10S-17W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ROSS C Well #: 3  
County: ROOKS Total Vertical Depth: 3600 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.375	3400		
PROD	4.5	3579		275 SX
SURF	8.625	153		120 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2017 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1128

Proposed Plugging Method: 2 3/8" tubing cemented in early 80's. No record transferred with well file.  
LKC perforations: 3449' - 3544'.  
Mechanical hold down on pump assembly left in hole at 3295'. Unable to move.  
Decided to P&A.  
Ordered 200 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 11/10/2017 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tied onto 8 5/8" surface casing and had instant pressure of 500 psi. Tied onto 4 1/2" backside with instant pressure of 500 psi. Hooked to tubing and pumped 75 sx cement with no hulls followed by 85 sx cement w/350 # hulls scattered in cement. Pressured to 1000 psi. Shut in pressure 500 psi.

Perfs:

Top	Bot	Thru	Comments
3540	3544		
3518	3520		
3494	3498		
3474	3484		
3449	3451		

KCC WICHITA  
DEC 04 2017  
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 3191

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

NOV 20 2017