

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20959-00-01
Spot: SENESENW Sec/Twnshp/Rge: 34-12S-32W
1896 feet from N Section Line, 2374 feet from W Section Line
Lease Name: SMITH Well #: 1-34
County: LOGAN Total Vertical Depth: 4670 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>9855</u>	PROD	5.5	4666		175 SX
Op Name: <u>GRAND MESA OPERATING COMPANY</u>	SURF	8.625	210		165 SX
Address: <u>1700 N WATERFRONT PKWY BLDG 600</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2017 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING COMP Phone: (620) 617-3357

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1000 # gel and 500 # hulls.
8 5/8" surface casing set at 210' w/165 sx cement.
5 1/2" production casing set at 4666' w/175 sx cement.
DV Tool set at 2531' w/300 sx cement.
TD 4670', PBSD 4656'.
Perforations: Toronto: 3964' - 3970' and Johnson: 4550' - 4555'.
Top down plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2017 11:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 5 1/2" production casing and pumped 100 sx cement w/500 # hulls followed by 1000 # gel and 255 sx cement. Connected to 8 5/8" surface casing and pumped 5 sx cement pressured to 300 psi.
GPS: 38.96946N -100.86166W

Perfs:

Top	Bot	Thru	Comments
4550	4555		
3964	3970		

KCC WICHITA
DEC 04 2017
RECEIVED

INVOICED
JAN 02 2018

Remarks: SWIFT SERVICES CEMENT TICKET # 30,547

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

NOV 17 2017