

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24618-00-00
Spot: SWSENW Sec/Twnshp/Rge: 25-34S-3E
2930 feet from S Section Line, 3627 feet from E Section Line
Lease Name: CITY OF ARKANSAS CITY Well #: 1-25
County: COWLEY Total Vertical Depth: 3900 feet

Operator License No.: 35147
Op Name: GULF EXPLORATION, LLC
Address: 9701 N. BROADWAY EXTENSION
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	16	34		50 SX
PROD	4.5	1855		125 SX
SURF	8.625	344		215 SX
T1	2.375	1535		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/16/2017 8:00 AM
Plug Co. License No.: 8733 Plug Co. Name: JERRY DUNKIN, INC.
Proposal Rcvd. from: PAT MCGRAW Company: GULF EXPLORATION Phone: (405) 840-3371

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP SET WITHIN 50' OF 1550' W/ 25 SXS, PERF @ 344' & CIRCULATE TO SURFACE. RUN IN TUBING.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/17/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 1570', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PRESSURED CASING @ 300#, HELD OK. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 400'-401' (4 HOLES). SWEDGED INTO CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
1596	1598	TBG	

Remarks: CEMENT TICKET #3466-17

INVOICED
JAN 02 2018

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

JK