

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-21096-00-00  
Spot: SESESE Sec/Twnshp/Rge: 1-17S-10W  
338 feet from S Section Line, 360 feet from E Section Line  
Lease Name: STRATMANN Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3351 feet

Operator License No.: 9911  
Op Name: HAR-KEN AGENT, OK  
Address: PO BOX 1991  
OWENSBORO, KY 42302

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3103		
CIBP		3140		
CIBP		3230		
CIBP	5.5	3259		
PROD	5.5	3346	2020	125 SX
SURF	8.625	276		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2017 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: AS PER KCC RULES & REGS. WELL HAS 2 OTHER CIBP'S @ 3230' AND 3140'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/11/2017 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. SAND PERFS TO 3010' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 2020' AND PULL TO 1250' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL CASING TO 950' AND WAIT 1.5 HRS. TAG CEMENT AT 975'. PUMPED 35 SX'S COMMON WITH CC AT 950', PULLED CASING TO 325' AND CIRCUALTED CEMENT TO SURFACE. PULLED CASING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3346	3351	OH	
3261	3262	CSG	
3250	3252	CSG	
3143	3146	CSG	
3105	3110	CSG	
3083	3087	CSG	

Remarks: COPELAND CEMENT #45269. TA - N.O.V. WELL

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
JAN 02 2018