

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-01599-00-00

Spot: SWSWSESE

Sec/Twnshp/Rge: 11-24S-9E

200 feet from S Section Line, 1100 feet from E Section Line

Lease Name: OLSON-ANDERSON

Well #: 7

County: GREENWOOD

Total Vertical Depth: 2230 feet

Operator License No.: 3599

Op Name: JB NORDMEYER, LLC DBA OLSON-AN

Address: 2253 P RD

EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	6.625	2107		100 SX
------	-------	------	--	--------

SURF	8.25	1664		100 SX
------	------	------	--	--------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/28/2017 10:00 AM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: BARNEY NORDMEYER

Company:

Phone: (620) 583-4711

Proposed  
Plugging  
Method:

SET BRIDGE PLUG ABOVE BARTLESVILLE. PUMP 50' PLUG. PERFORATE ABOVE DOUGLAS FORMATION.  
PUMP GEL SPACING BETWEEN BARTLESVILLE AND DOUGLAS. PUMP 50' PLUG ABOVE DOUGLAS.  
PERFORATE AT 200' WITH GEL SPACING BETWEEN DOUGLAS AND 200'. PUMP CEMENT FROM 200' TO  
SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/28/2017 2:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1740', pumped 15 sxs cement pulled tubing to 1000'/pumped 15 sxs cement, pulled tubing to 216', pumped 125 sxs cement to surface, shot casing @ 1000' & 200', gel spacers between cement plugs,

Perfs:

Top	Bot	Thru	Comments
2183	2225		

RECEIVED  
KCC DIST #3

DEC 11 2017

CHANUTE, KS

MH

INVOICED

JAN 03 2018

Remarks:

Plugged through: TBG

District: 03

Signed

*Michael Heffern*  
(TECHNICIAN)



Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-28-17	1087	Olsen & Anderson #7				Greenwood	Ks
Customer			Safety Meeting	Unit #	Driver	Unit #	Driver
J B Nordmeyer oil				102	Rick		
Mailing Address				114	Alan M		
2253 P Rd				145	Allen B		
City	State	Zip Code					
Eureka	Ks	67045					

Remarks: Safety Meeting: Pick up to 2<sup>nd</sup> tubing. Pump 2 bbls Fresh water + Mix 300<sup>th</sup>  
Gal  
Spot 15 sks AT 1740'  
Spot 15 sks AT 1000'  
125 sks 216' To Surface  
Total 155 sks 69/40 Pozmix cement 4 1/2 Gal  
Job Complete Rig down

Thank You

[illegible]

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.