

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-01600-00-00

Spot: SESESWSE

Sec/Twnshp/Rge: 11-24S-9E

182 feet from S Section Line, 1535 feet from E Section Line

Lease Name: OLSON-ANDERSON

Well #: 3

County: GREENWOOD

Total Vertical Depth: 2205 feet

Operator License No.: 3599

Op Name: JB NORDMEYER, LLC DBA OLSON-AN

Address: 2253 P RD  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	2079		100 SX
SURF	8.25	1636		100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/29/2017 12:00 PM

Plug Co. License No.: 99973

Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC

Proposal Rcvd. from: BARNEY NORDMEYER

Company:

Phone: (620) 583-7548

Proposed Plugging Method: SET BRIDGE PLUG ABOVE BARTLESVILLE. PUMP 50' PLUG. PERFORATE ABOVE DOUGLAS FORMATION. PUMP GEL SPACING BETWEEN BARTLESVILLE AND DOUGLAS. PUMP 50' PLUG ABOVE DOUGLAS. PERFORATE AT 200' WITH GEL SPACING BETWEEN DOUGLAS AND 200'. PUMP CEMENT FROM 200' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/29/2017 4:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 2002', pumped 15 sxs cement, pulled tubing to 1000', pumped 15 sxs cement, pulled tubing to 215', pumped 80 sxs cement to surface, casing shot @ 1000' & 200', gel spacers between cement plugs.

RECEIVED  
KCC DIST # 3  
DEC 11 2017  
CHANUTE, KS

MH

INVOICED  
JAN 03 2018

Remarks:

Plugged through: TBG

District: 03

Signed

*Mike Heffern*  
(TECHNICIAN)



Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-29-17	1087	Olsen ANDERSON # 3				GW	Ks
Customer J B Nordmeyer OIL			Safety Meeting KM AM JH GM	Unit #	Driver	Unit #	Driver
Mailing Address 2253 P. Rd				104	ALAN M.		
				114	JASON H.		
				145	KEVIN M.		
				127 P.U.	GREG M.		
City EUREKA	State KS	Zip Code 67045					

Remarks: Safety Meeting: Rig up to 2<sup>3</sup>/<sub>8</sub> tubing. Spot Cement Plugs AS Following. 7" Casing

[illegible]

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.