

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19432-00-00
Spot: SESWSENW Sec/Twnshp/Rge: 5-35S-13E
2822 feet from S Section Line, 3551 feet from E Section Line
Lease Name: J R JYDER-STEINBERGER UNI Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 6 | 750 | | 0 SX |
| SURF | 10 | 40 | | 0 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method:

| |
|--|
| Surface cement unknown.Plug according to KCC specifications. |
|--|

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 09/25/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" inside 2" to 660' gelled hole and spotted 15 sack plug. Pulled 1" and shot tubing off. Pulled 500' of 2". Perforated casing at 275'. Ran 1" back into 500' and spotted 30 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 90 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:


| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 700 | 710 | | |

RECEIVED
KCC DIST # 3
DEC 19 2017
CHANUTE, KS
DS
INVOICED
JAN 03 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)