

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19448-00-00
Spot: NWNWENW Sec/Twnshp/Rge: 5-35S-13E
5113 feet from S Section Line, 3806 feet from E Section Line
Lease Name: J R HYDER-STEINBERGER UN Well #: 21
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	750		0 SX
SURF	10	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown.Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Cleaned hole out. Well had several strings of pipe in it. Ran 1" to 700' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 275'. Ran 1" back into 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 170 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
700	710		


RECEIVED
KCC DIST #3
DEC 19 2017
CHANUTE, KS
DS
INVOICED
JAN 03 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)