

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-40588-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 6-35S-13E  
4476 feet from S Section Line, 522 feet from E Section Line  
Lease Name: BUCKLES & STOUGH Well #: 5  
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	750		0 SX
SURF	10	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/03/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:


Ran 1" to 704' gelled hole and spotted 20 sack plug. Pulled 1" and shot tubing off at 480'. Pulled 2" out of well. Ran 1" back into 480 and spotted 20 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 160 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
700	710		

RECEIVED  
KCC DIST # 3  
DEC 19 2017  
CHANUTE, KS  
DS  
INVOICED  
JAN 03 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.  
Plugged through: TBG

District: 03 Signed   
(TECHNICIAN)