

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40590-00-00
Spot: NENWNENE Sec/Twnshp/Rge: 6-35S-13E
5125 feet from S Section Line, 790 feet from E Section Line
Lease Name: BUCKLES & STOUGH Well #: 8
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	750		0 SX
SURF	10	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: _____
Surface cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 10/02/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Washed 1" down 2" to 640' gelled hole and spotted 20 sack plug. Pulled 1". Shot tubing at 380'. Tubing was rotten and wouldn't come out of well. Ran 1" down inside of tubing to 380' and 1" down backside of tubing to 275'. Circulated cement to surface inside and outside of tubing. Pulled 1" and topped well off. A total of 162 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:


Top	Bot	Thru	Comments
700	710		

RECEIVED
KCC DIST # 3
DEC 19 2017
CHANUTE, KS
DS
INVOICED
JAN 03 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)