

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40583-00-00
Spot: SWSENE Sec/Twnshp/Rge: 6-35S-13E
4222 feet from S Section Line, 362 feet from E Section Line
Lease Name: CLEVINGER Well #: C3
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	750		0 SX
SURF	10	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 10/04/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" into 730' gelled hole and spotted 20 sack plug. Pulled 1" and shot 2" tubing at 300'. Pulled 300' of 2" tubing. Ran 1" back into 300' and circulated cement to surface. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
700	710		

RECEIVED
KCC DIST #3
DEC 19 2017
CHANUTE, KS
DS
INVOICED
JAN 03 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)