

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-23560-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 6-34S-12E
2794 feet from S Section Line, 5121 feet from E Section Line
Lease Name: PADGETT Well #: 4C
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1806		0 SX
SURF	8.625	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 11/16/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1030' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. Ran 1/2" down backside to 37' and circulated cement to surface. A total of 42 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1035	1050		

RECEIVED
KCC DIST #3
DEC 20 2017
CHANUTE, KS
DISOICED
JAN 03 2018

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)