

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21076-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 16-15S-33W
2139 feet from N Section Line, 2303 feet from E Section Line
Lease Name: GERBER Well #: 1-16
County: LOGAN Total Vertical Depth: 4665 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 4900 WOODWAY DR SUITE 880
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4648		175 SX
SURF	8.625	216		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2017 8:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: BOB GLENN Company: LANDMARK RESOURCES, INC. DB Phone: (316) 755-3523

Proposed Plugging Method:
DV Tool at 2356' w/500 sx cement.
Set CIBP at 4250' w/2 sx cement on top.
Ordered 250 sx 60/40 pozmix 4% gel cement, 300 # hulls and 1200 # gel.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2017 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Set CIBP at 4250' w/2 sx cement on top. Ran tubing to 4225'. Basic pumped 1200 # gel. Pulled tubing to 2440'. Basic pumped 180 sx cement w/200 # hulls. Cement circulated. PTOH. Topped off 4 1/2" casing with 20 sx cement. Casing full. Hooked up to backside and pumped 4 sx cement. Maximum pressure 400 psi. Shut in pressure 400 psi.

Perfs:

Top	Bot	Thru	Comments
4442	4448		
4366	4369		
4338	4344		
4314	4316		
4313	4315		
4281	4284		
0			

Remarks:

Plugged through: TBG

District: 04

Signed



Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

DEC 17 2017

Form CP-2/3

INVOICED
JAN 03 2018