

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-203-20269-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 27-19S-35W
1070 feet from S Section Line, 1811 feet from E Section Line
Lease Name: GEYER A Well #: 1-27
County: WICHITA Total Vertical Depth: 5100 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3164		
DVT	4.5	2324		WITH 400 SX CMT
PROD	4.5	5002	0	WITH 330 SX CMT
SURF	8.625	370		WITH 240 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2017 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: MIKE KETTERLING Company: LARIO OIL & GAS Phone: (620) 277-2149

Proposed Plugging Method: PUMP 35 SX CMT WITH 150# HULLS. 23 BBL WATER SPACER BACK T 2500'. PUMP 165 SX CMT FROM 2500' TO 0'. ATTEMPT TO GET A LITTLE CMT DOWN THE ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2017 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT WITH 200# HULLS FROM 4546' TO 4000'. PUMP 23 BBL SPACER FROM 4000' TO 2550'. PUMP 175 SX CMT FROM 2550' TO 0'. PRESSURE TO 450#. HOLDING. PUMP 5 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4540	4546		

INVOICED
JAN 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY OES.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
NOV 27 2017
KCC DODGE CITY