

1 120782

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,902.0000

NE SW SW, SEC. 26, T 21 S, R 12 W ~~12~~

990 feet from S section line

4290 feet from E section line

Lease Name Dennis Well # 6

County Stafford 118.56

Well Total Depth 3648 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 304

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Operator: L.D. Drilling, Inc.

Name:

Address RR 1, Box 183 B

Great Bend, KS 67530

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 12 Month: 4 Year: 1993

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 610-632'

1st plug at 640' with 50 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 12 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 640' with 50 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied.

APR 14 1993

**INVOICED**

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 4-22-93

CONSERVATION DIVISION  
Wichita, Kansas

Signed Duane Rankin  
(TECHNICIAN)

WV. NO. 37600

4-12 JUN 23 1993

EFFECTIVE DATE: 4-7-93  
DISTRICT # 1  
Yes  No

State of Kansas  
NOTICE OF INTENTION TO DRILL 185-22,902

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: April 5 1993  
month day year

Section NE SW SW Sec 26 Twp 21 S. Rg 12 East West

OPERATOR: License # 6039  
Name: L. D. Drilling, Inc.  
Address: R.R. 1 Box 183 B  
City/State/Zip: Great Bend, Kansas 67530  
Contact Person: L. D. Davis  
Phone: (316) 793-3051

990 feet from South North line of Section  
 4290 feet from East West line of Section  
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Stafford  
Lease Name: Dennis Well # 6  
Field Name: Max North

CONTRACTOR: License # 6039  
Name: L. D. Drilling, Inc.

Is this a Prestrated/Spaced Field? ... yes X no   
Target Formation(s): Arbuckle  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: APPROX. 1833' feet MSL

Well Drilled For: Well Class: Type Equipment:  
 Oil  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OMSO  Disposal  Wildcat  Cable  
 Seismic;  # of Holes  Other

Water well within one-quarter mile:  yes  no  
Public water supply well within one mile: ... yes  no  
Depth to bottom of fresh water: 180'  
Depth to bottom of usable water: 220'  
Surface Pipe by Alternate: X. 1 ... 2  
Length of Surface Pipe Planned to be set: 250'  
Length of Conductor pipe required: none  
Projected Total Depth: 3700'  
Formation at Total Depth: Arbuckle  
Water Source for Drilling Operations:  
 well ... farm pond ... other

If CWD: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes  no   
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_

DWR Permit #: \_\_\_\_\_  
Will Cares Be Taken?: ... yes  no   
If yes, proposed zone: \_\_\_\_\_

Exp. 10/2/93

AFFIDAVIT

250' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Greg Davidson INIT. GDW  
SPUD DATE 4-6-93  
LENGTH SURFACE PLANNED 200'  
RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8" @ 304 CONDUCTOR ANHYDRITE T- 610 B- 632 ELEVATION  
TD 3648 FORMATION \_\_\_\_\_  
RAN PIPE @ SX DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_ SX Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 640 Ft. W/ 50 SX  
1/2 Base Anyh. @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Bottom Surface @ 330 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_ Hauling \_\_\_\_\_)  
TECHNICIAN DR DATE 4-12-93  
TYPE OF CEMENT \_\_\_\_\_ DATE 02/40/696  
TARTRIC ACID \_\_\_\_\_ (AM/PM) DATE 4-12  
COMPLETION TIME \_\_\_\_\_ (AM/PM) DATE 4-12  
COMPLETION TIME \_\_\_\_\_ (AM/PM) DATE 4-12  
CEMENT COMPANY Allied  
Banker Saw