

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21546-00-00
Spot: SWSESW Sec/Twnshp/Rge: 26-21S-12W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SIEFKES Well Number: 4
County: STAFFORD Total Vertical Depth: 3700 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 8 120.25
Surface Casing: Size 8.625 feet: 255 WITH 190 SX CMT
Production: Size 5.5 feet: 3697 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/21/2002 1:45 PM.

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 33610' & 5 SX CMT. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/21/2002 3:30 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3360-62'. ANHYDRITE AT 608'. SANDED TO 3300' & 5 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 630' WITH 200# HULLS - 10 SX GEL - 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

MAY 29 2002
S-29-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 5-30-02 MAY 24 2002
INV. NO. 2002061854 MP

Form 2123