

1 040581

10-17

129R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,848.0000

NW NE NE SW, SEC. 26, T. 21 S, R. 12 W/E

2390 feet from S section line

3040 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Drach Well # A-3

Operator: Phillips Petroleum Company
Name &

County Stafford 118.65

Address Rt. 3, Box 20-A

Well Total Depth 3651 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 17 Month: 10 Year: 19 91

Plugging proposal received from Milard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3650' w/260 sx cement, Perfs at 3255-3494', 3610-3650'

1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 17 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3245' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 11 sx gel, 50 sx cement,

11 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 350 psi and shut in 200 psi.

OCT 22 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2205.75' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 11-14-91

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 33716