

To: 1 120470  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 150'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15 Drill Completion Date 12/2/48  
E of C E/2 SEC. 27, T 21 S, R 13 W XX  
2640 feet from S section line  
1170 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30385  
Operator: Liedtke Operating Corporation  
Name & Address 370 17th Street, Suite 5020  
Denver, CO 80202-9789

Lease Name Gates Well # 11  
County Stafford 122.29  
Well Total Depth 3763 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Chase Well Service, Inc. License Number 6123

Address P.O. Box 355, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 20 Month: 9 Year: 19 90

Plugging proposal received from Charles Steincamp

(company name) Chase Well Service (phone) 316-793-7456

were: 5 1/2" at 3759' w/200 sx cement, PBD 3726', Perfs at 3648-3662', 5 1/2" squeezed from 392-544' w/250 sx cem.

1st plug perforate at 730', pump 2 sx hulls and 30 sx cement through tubing on bottom, fill hole with gel,

2nd plug pull tubing to 730', circulate cement,

3rd plug pump 100 sx cement down 8 5/8" X 5 1/2".

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 20 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug perforated 5 1/2" casing at 703', ran tubing to 3634' and pumped in 150 lbs. hulls, layed down 2 joints and pumped in 30 sx common cement,

2nd plug layed down 8 joints and pumped in 19 sx Bentonite, layed down 23 joints and circulated cement (60/40 Pozmix 6% gel) at 713' with 65 sx;

3rd plug pulled all tubing and squeezed 5 1/2" casing with 50 sx cement.

Pumping pressure 700 psi and shut in 400 psi. 4th plug squeezed through 8 5/8" X 5 1/2" annulus with 10 sx cement. Shut in pressure 700 psi.

Remarks: No casing recovery. Cemented by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-90  
INV. NO. 29480

SEP 27 1990

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas