

To: 1 120576
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Operator: A.L. Abercrombie, Inc.
Name & Address Rt 1, Box 56
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 4 Month: 6 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3750' w/175 sx cement, PBTD 3724', Perfs at 3404-3716' (6 sets)

1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 4 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3350' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2122' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 6-20-91

Signed Dennis Rankin
(TECHNICIAN)

INV. NO. 32188