

To: 1 120575
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Operator: A.L. Abercrombie, Inc.
Name & Address Rt 1, Box 56
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 4 Month: 6 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3669' w/150 sx cement, PBSD 3470', Perfs at 3455-60'

1st plug sand back to 3400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 4 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3400' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2500' of 5 1/2" casing

(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 6-20-91

Signed Dawn Rankin
(TECHNICIAN)

WV. NO. 32186

6-4 15.185.30278.0000
API NUMBER 15- Drilled 1/26/66
NW NE NW, SEC. 27, T 21 S, R 13 W/EX
4950 feet from S section line
3630 feet from E section line
Lease Name Linke Well # 1
County Stafford 120.08
Well Total Depth 3695 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 320

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1991

CONSERVATION DIVISION
WICHITA, KANSAS