

6-4 15.185.30281.0001

API NUMBER 15- D-24,764

To: 1 120577
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 N/2 NW, SEC. 27, T 21 S, R 13 W/E

4290 feet from S section line

3960 feet from E section line

Lease Name Linke Well # 2

County Stafford 110.24

Well Total Depth 3392 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 273

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393

Operator: A.L. Abercrombie, Inc.
Name & Address
Rt 1, Box 56
Great Bend, KS 67530

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 4 Month: 6 Year: 1991

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3750' w/175 sx cement, Open hole 3750-3892'

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 4 Month: 6 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-450 psi and shut in 150 psi.

RECEIVED STATE CORPORATION COMMISSION

JUN 13 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1300' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 6-20-91

Signed [Signature] (TECHNICIAN)

INV. NO. 32187