

1 080531

Docket No. D-01,878 15.185.01749.0002221 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 3-20-34
C SW NE, SEC. 27, T 21 S, R 13 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5398
Operator: Arco Oil and Gas Company
Name & Address P. O. Box 3708
Enid, OK 73702

Lease Name Gates Unit Well # B-1 SWD
County Stafford 135.36
Well Total Depth 4165 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 12 1/2" feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well x D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Arco Oil & Gas 1 License Number 5398

Address P. O. Box 3708, Enid, OK 73702

Company to plug at: Hour: 9:30 am Day: 9 Month: June Year: 19 86

Plugging proposal received from Robert L. McGlinn

(company name) Arco (phone) 316-793-5467

were: 7" at 3662' 5 1/2" liner at 3340-3848' PBTD 4165' Open hole from 3848-4165'

1st plug set CIBP at 3294' Top of fish at 690'

2nd plug pull 7" casing from 425', go back to top of cement and circulate hole.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:15 pm Day: 9 Month: June Year: 19 86

ACTUAL PLUGGING REPORT RIH with tubing. Tbg set down at 421'. POH with tubing. Pull 7"

OD csg. 423'. RIH with 706' 2 3/8" OD Tbg. Mix and pumped 100 sx 60/40 Pozmix 6% gel 3%

CC. est top 500'. POH with tubing tp 492' mix and pumped 700# hulls and 100 sx 60/40 Pozmix

6% gel 3% CC. est top 300'. POH with tubing tp 312' mix and pumped 225 sx 60/40 Pozmix

6% gel and 3% CC. Cement circulated to surface. POH with tubing. Top off 12 1/2".

Remarks: Used 60/40 Pozmix 6% gel 3% cc. by Allied. Recovered 432' 7" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging operation

INVOICED

RECEIVED
JUL - 8 1986

J. H. Metz
(TECHNICIAN)

DATE JUL 10 1986

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

INV. NO. 14309