

10-7

1 120147

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15 - Drill Completion Date 3/24/58  
100' E C  
NE NW NE, SEC. 27, T 21 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3290  
Operator: Hondo Oil & Gas Company  
Name & Address: 601 South Harding Street  
Enid, OK 73703

4950 feet from S section line  
1550 feet from E section line

Lease Name R.C. Gates Well # 17  
County Stafford 121.71  
Well Total Depth 3745 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635  
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 7 Month: 10 Year: 19 88

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 7" at 3745' PBTD 3694' Perfs at 3333-3688' (7 sets)  
1st plug sand back to 3300' and dump 7 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 175 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 7 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 2625' and dumped 6 sx cement on  
top of sand through bailer.

2nd plug pumped in 10 3/4" surface casing with 400 lbs. hulls, 20 sx gel, 50 sx cement,  
10 sx gel, 200 lbs. hulls and 175 sx cement.

Recovered 1500' of rods and 3400' of tubing.

Pumping pressure 0-600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 213' of casing  
(If additional description is necessary, use BACK of this form)

INVOICED

DATE 10-19-88

INV. NO. 22594

Signed Duane Rankin  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
10-13-88  
CONSERVATION DIVISION  
Wichita, Kansas